



NOTES:

1. CYLINDER MATERIAL SHALL BE THE THINWALL A.B.S. OR P.V.C. PLASTIC PIPE.
2. TOP OF MONUMENT CORE SHALL BE FINISHED SMOOTH AND ROUNDED WITH NO CONCRETE ABOVE THE EDGE OF THE BRASS SURVEY MARKER.
3. THE BRASS SURVEY DISK SHALL BE PROVIDED BY THE PROJECT ENGINEER AND PUNCHED.

COUNTY OF SONOMA DEPARTMENT OF TRANSPORTATION AND PUBLIC WORKS		
SURVEY MONUMENT		
DATE: MAY 2004	REVISED: MAY 2007	
APPROVED BY:	SCALE: NONE	DRAWING NO. 218