



NOTES:

1. THIS DRAWING REPRESENTS TYPICAL CONCRETE AND BEDDING CONSTRUCTION REQUIREMENTS FOR ALL TYPES OF CURB RAMPS.
2. CONCRETE SHALL CONTAIN SIX SACKS OF CEMENT PER CUBIC YARD.
3. SEE GENERAL NOTES ON SONOMA COUNTY DEPARTMENT OF TRANSPORTATION AND PUBLIC WORKS CONSTRUCTION STANDARDS DRAWING 224B.

COUNTY OF SONOMA DEPARTMENT OF TRANSPORTATION AND PUBLIC WORKS		
CURB RAMP EXCEPTIONS AND SUPPLEMENTAL REQUIREMENTS TO STATE STANDARD PLANS A88A AND A88B		
DATE: MAY. 2004	REVISED: JUN. 2006	
APPROVED BY:	SCALE: NONE	DRAWING NO. 224A