



NOTES:

1. IF THERE IS NO DIKE OR CURB, AND AC WALKWAY IS ABOVE EXISTING GROUND, INSTALL A 2" X 6" HEADER BOARD ON BOTH SIDES. HEADER BOARD SHALL BE REDWOOD OR PRESSURE TREATED FIR.
2. IF AC WALKWAY IS BELOW EXISTING GROUND, HEADER BOARDS MAY BE ELIMINATED.
3. ASPHALT CONCRETE SHALL BE A MINIMUM OF 2-1/2" THICK AT DRIVEWAYS.
4. INCREASE AGGREGATE BASE TO 6" AT DRIVEWAYS.
5. BASE MATERIAL SHALL BE COMPACTED TO A RELATIVE DENSITY OF 95%.

COUNTY OF SONOMA DEPARTMENT OF TRANSPORTATION AND PUBLIC WORKS		
ASPHALT CONCRETE WALKWAY		
DATE: MAY 2004	REVISED:	
APPROVED BY:	SCALE: NONE	DRAWING NO. 228